

A. EXTRAS DE ARMATURA, PLASE SUDATE, LAMINATE - GRADINITA 12

1.Extras de armatura-fundatii scara

Marca	Elementul		Nr. piese asemenea		A unei bare	LUNGIMI ÎN METRII									
			Într-un element	În toate elem.		OB 37		PC 52							
	Denumir	φ				φ 6	φ 8	φ 8	φ 10	φ 12	φ 14	φ 16	φ 18	φ 20	φ 22
1	Fundatii Scara F1 1,40 x 1,40 4 buc	14	22	88	1,25						110				
2		14	13	52	2,00						104				
3		10	5	20	3,36				67,2						
4		12	14	56	3,20					123,2					
5		10	10	40	2,20				88						
6		10	8	32	1,52				48,65						
Lungimi pe diametre m									204	123,2	214				
Greutate pe metru kg									0,617	0,888	1,210				
Greutate pe diametre kg									126	110	259				
TOTAL kg									495						

2. plasa STNB φ 6x200/φ 6x200 - la platforma scarii S = 30,60 mp

3 buc. – 2000 x 5000 mm = 22,2 kg/ buc.

G total 1 = 66,6 kg

3. plasa STNB φ 6x200/φ 6x200 - la zid trotuar S = 8,00 mp,

1 buc. – 2000 x 5000 mm = 22,2 kg/ buc.

G total 2 = 22.2 kg

4. plasa STNB φ 6x200/φ 6x200 - la fundatie gard S = 18,00 mp

2 buc. – 2000 x 5000 mm = 22,2 kg/ buc.

G total 2 = 44.4 kg

5. plasa STNB φ 6x100/φ 6x100 - la camasuire ziduri S = 18.0 mp

2 buc. – 2000 x 5000 mm = 44,4 kg/ buc.

G total 3 = 88.8 kg

6.Extras de laminate (scara secundara, gard)

Poz.	Denumire	Lungime mm	SREN	Buc.	Greutate (kg/m)	Greutate totală (kg)
P1	25x25x3	2000	EN10210-1	1	1,89	3,78
P2	60x60x5	3000	EN10210-1	4	8.13	97.56
TOTAL (kg)					101.34	

B.EXTRAS DE MATERIAL LEMNOS LUCARNA / COMPLETARE SARPANTA, PLANSEU

Poziție	Element	Bucăți	Secțiune transversală b x h - cm	Lungime efectivă -m-	Lungime livrare -m-	Volum -mc-
P1	Capriori	3	10x15	5,0	5,0	0,225
P2	Pop	1	15x15	1,70	4,0	0,09
P3	Pana	1	15x15	2,10	15,0	0,1125
P4	Capriori	3	8x12,5	1,25	5,0	0,15
P5	Clesti	4	2,8x15	1,65	3,50	0,06
P6	Grinzi	17	10x15	4,0	4,0	1,02
TOTAL: (mc)						1,65
Rotund						1,70

Astereală 2,5 mm – 22,0 mp;